Accompanying Construction Activities

It is likely that the following activities would necessitate additional temporary lane and/or parking restrictions, similar to those shown on Construction Staging Plan, on City Streets and/or NYS Route 33:

- Bridge removals and temporary bridge installations
- Staged bridge construction (Best Street)
- Utility relocations and installations
- Large equipment and material deliveries
- Mechanical utility installations, including underground equipment and distribution buildings

If road or sidewalk closures or parking restrictions are required to complete these, or any other activities, mitigation measures (detours and alternate parking arrangements) would be implemented.







